

# APPENDIX E

## Outdoor Lighting Standards



**GENERAL NOTES**

**I. OVERALL NOTES**

- A. PRIOR TO BEGINNING ANY WORK OR ORDERING ANY MATERIALS, THE CONTRACTOR SHALL COORDINATE THE STRUCTURAL DRAWINGS WITH ALL OTHER TRADES. NOTIFY THE OWNER AND THE ENGINEER OF RECORD OF ANY DISCREPANCIES OR POSSIBLE DEFICIENCIES.
- B. PRIOR TO STARTING WORK, THE CONTRACTOR SHALL VERIFY THE EXISTING SITE CONDITIONS AND CONSTRAINTS AS WELL AS EXISTING BUILDING LOCATION, DIMENSIONS, AND ELEVATIONS, IF ANY.
- C. NO FIELD REVISIONS OR MODIFICATIONS TO ANY STRUCTURAL COMPONENT SHALL BE PERFORMED WITHOUT PRIOR APPROVAL BY THE ENGINEER OF RECORD.
- D. PLANS AND DETAILS SHALL NOT BE SCALED FOR DETERMINATION OF LENGTHS, QUANTITIES, OR CONFIGURATION OF MATERIALS.

**II. COORDINATION WITH OTHER TRADES**

- A. THE CONTRACTOR SHALL SUPPLY ALL ITEMS FOR ATTACHING MECHANICAL AND ELECTRICAL EQUIPMENT TO THE STRUCTURE TO RESIST ALL LOADS, INCLUDING SEISMIC FORCES. COORDINATE THE LOCATION(S) AND REQUIRED ATTACHMENT(S) WITH THE STRUCTURE. REFER TO THE ELECTRICAL AND MECHANICAL DOCUMENTS FOR ADDITIONAL REQUIREMENTS.
- B. COORDINATE AND PROVIDE SLEEVE LAYOUTS FOR ALL PIPES, CONDUITS, OR ANY OTHER ITEMS PENETRATING THROUGH STRUCTURAL MEMBERS. LAYOUTS ARE TO BE SUBMITTED TO AND APPROVED BY THE ENGINEER OF RECORD PRIOR TO CONSTRUCTION.


**III. GEOTECHNICAL NOTES**

- A. THE FOUNDATIONS FOR THIS STRUCTURE WE REDESIGNED BASED UPON THE PRESUMPTIVE ALLOWABLE VALUES AS DESCRIBED IN THE 2009 INTERNATIONAL BUILDING CODE, TABLE 1806.2 "PRESUMPTIVE LOAD-BEARING VALUES" FOR CLAY, SANDY CLAY, SILTY CLAY, CLAYEY SILT, SILT, AND SANDY SILT. SHOULD ACTUAL SITE CONDITIONS VARY FROM THIS, THE FOUNDATION SHALL BE REDESIGNED.

**IV. REINFORCED CONCRETE NOTES**

- A. ALL REINFORCED CONCRETE SHALL CONFORM TO ALL REQUIREMENTS OF ACI 301 "SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS", LATEST EDITION INCLUDING AMENDMENTS, AND ACI 318 "BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE", EDITION REFERENCED IN THE 2009 INTERNATIONAL BUILDING CODE.
- B. TOLERANCES FOR CONCRETE MEMBERS AND COMPONENTS SHALL CONFORM TO ACI 117 "SPECIFICATION FOR TOLERANCES FOR CONCRETE CONSTRUCTION AND MATERIALS."
- C. DETAILING OF CONCRETE REINFORCEMENT AND ACCESSORIES SHALL CONFORM TO ACI 315 "DETAILS AND DETAILING OF CONCRETE REINFORCEMENT."
- D. U.N.O., CONCRETE SHALL HAVE SAND AND CRUSHED STONE OR GRAVEL AGGREGATE AND TYPE I, II, OR III PORTLAND CEMENT. THE CONCRETE SHALL HAVE A MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 3,500 PSI AND A MAXIMUM WATER/CEMENTITIOUS MATERIALS RATIO OF 0.50, AND SHALL BE AIR ENTRAINED WITH AIR CONTENT OF 6% ±1.5%.
- E. NORMAL WEIGHT AGGREGATE SHALL CONFORM TO ASTM C33.
- F. SLUMP OF CONCRETE SHALL NOT EXCEED 3" AT THE END OF THE TRUCK OR PUMP HOSE (PER ACI 211.1 TABLE 6.3.1). SLUMP LOSS DUE TO PUMPING SHALL BE ACCOMMODATED. IF A SUPERPLASTICIZER OR MID-RANGE WATER REDUCING ADMIXTURE IS USED IN THE MIX DESIGN, THE SLUMP SHALL NOT EXCEED 8" AFTER ADDITION OF THE ADMIXTURE. DO NOT ADD WATER TO CONCRETE AFTER ADDING WATER-REDUCING ADMIXTURES TO THE MIX.
- G. U.N.O., ALL CONCRETE REINFORCING BARS SHALL CONFORM TO ASTM A615, GRADE 60 AND BE OF DOMESTIC MANUFACTURE. REINFORCING BARS TO BE WELDED SHALL CONFORM TO THE REQUIREMENTS OF ASTM A706, GRADE 60. WELDING TO REINFORCING BARS NOT SHOWN ON THE DRAWINGS, SHALL NOT BE PERMITTED. ELECTRICAL GROUNDING AND OTHER REQUIRED CONNECTIONS TO REINFORCING BARS SHALL BE ATTAINED VIA CLAMPS OR OTHER MANUFACTURED CONNECTIONS.
- H. REINFORCING SHALL BE SUPPORTED AND SECURED IN ITS PROPER LOCATION TO PREVENT DISPLACEMENT DURING PLACEMENT OF CONCRETE.
- I. THE CONTRACTOR SHALL VERIFY WITH ALL DISCIPLINES THE LOCATIONS OF ALL REQUIRED OPENINGS, SLEEVES, CAST-IN-PLACE ANCHORS OR HANGERS, SLAB DEPRESSIONS, INSERTS AND ANY OTHER ITEM TO BE CAST INTO THE CONCRETE.
- J. ALL HIGH-STRENGTH GROUT SHALL BE PREPACKAGED, NON-METALLIC, AND NON-GASEOUS. IT SHALL BE NON-SHRINK ACCORDING TO ASTM C-1107 OR CRD-C-821. GROUT SHALL OBTAIN A MINIMUM COMPRESSIVE STRENGTH OF 7,000 PSI IN 28 DAYS AND SHALL NOT BLEED. GROUT SHALL BE MOIST CURED FOR A MINIMUM OF 24 HOURS AFTER PLACEMENT. SUBMIT CERTIFIED, INDEPENDENT TEST DATA FOR APPROVAL.

# ROADWAY LIGHT POLE FOUNDATION (WITH CLAMSHELL BASE)




LIGHT POLE REACTIONS AT T.O. FOUNDATION				
POLE SIZE	BENDING MOMENT (F/ILBS)	TORSION (F/ILBS)	SHEAR FORCE (LBS)	AXIAL FORCE (LBS)
REFER LIGHT POLE DESCRIPTIONS	17,596	1149	1089	1055

**NOTES:**  
REACTIONS TO FOUNDATIONS SHOWN ARE A PROVIDED BY LIGHT MANUFACTURER. THE WORSE CASE LOADING IS NOTED. SHOULD THIS REACTION FROM ANY FIXTURE EXCEED THE VALUES NOTED, THE FOUNDATIONS SHALL BE RE-EVALUATED.


**LIGHT POLE DESCRIPTIONS**

- POLE BASE: NY24CSBCADBH - (CLAMSHELL BASE)
- POLE: FL210-700E210-P16-BZ, FL210-700E210-P16-(2)BAP-BZ, FL210-700E210-P16-(4)BAP-BZ
- POLE ARMS: ATC51/1CADBH-QSM OR ATC102/2CADBH-QSM
- BANNERS ARMS: (2) OR (4) BA30BOH4BZ
- FIXTURES: (1) OR (2) ESL P30S 40K AS BZ TG 3 S BHDF13 200 BZ



CEC CORPORATION  
1655 W. MEMORIAL ROAD  
OKLAHOMA CITY, OKLAHOMA 73142  
P. 405.533.4200  
WWW.CONNECTCEC.COM

STATE OF OK CERTIFICATE OF AUTHORIZATION  
CHRYSTOPHER SWIDER  
C.E.P. No. 23089  
THIS DRAWING IS THE PROPERTY OF CEC. ANY REPRODUCTION OR USE OF THIS DRAWING WITHOUT THE PERMISSION OF CEC IS PROHIBITED.



REVISION HISTORY	
NO.	DESCRIPTION

DATE	DATE	DESCRIPTION

100% CONSTRUCTION DOCUMENTS	DATE	DESCRIPTION

DATE	DESIGNED BY	DRAWN BY	APPROVED BY	SCALE
03/11/2016	C.L.S.	J.D.H.	C.L.S.	AS NOTED
14/25/16	C.L.S.	J.D.H.	C.L.S.	AS NOTED

**OSU ROADWAY LIGHT POLE FOUNDATIONS**

STILLWATER, OKLAHOMA

FOUNDATION DETAILS

SHEET  
**S1**



**GENERAL NOTES**

**I. OVERALL NOTES**

- A. PRIOR TO BEGINNING ANY WORK OR ORDERING ANY MATERIALS, THE CONTRACTOR SHALL COORDINATE THE STRUCTURAL DRAWINGS WITH ALL OTHER TRADES, NOTIFY THE OWNER AND THE ENGINEER OF RECORD OF ANY DISCREPANCIES OR POSSIBLE DEFICIENCIES.
- B. PRIOR TO STARTING WORK, THE CONTRACTOR SHALL VERIFY THE EXISTING SITE CONDITIONS AND CONSTRAINTS AS WELL AS EXISTING BUILDING LOCATION, DIMENSIONS, AND ELEVATIONS, IF ANY.
- C. NO FIELD REVISIONS OR MODIFICATIONS TO ANY STRUCTURAL COMPONENT SHALL BE PERFORMED WITHOUT PRIOR APPROVAL BY THE ENGINEER OF RECORD.
- D. PLANS AND DETAILS SHALL NOT BE SCALED FOR DETERMINATION OF LENGTHS, QUANTITIES, OR CONFIGURATION OF MATERIALS.

**II. COORDINATION WITH OTHER TRADES**

- A. THE CONTRACTOR SHALL SUPPLY ALL ITEMS FOR ATTACHING MECHANICAL AND ELECTRICAL EQUIPMENT TO THE STRUCTURE TO RESIST ALL LOADS, INCLUDING SEISMIC FORCES. COORDINATE THE LOCATION(S) AND REQUIRED ATTACHMENT(S) WITH THE STRUCTURE. REFER TO THE ELECTRICAL AND MECHANICAL DOCUMENTS FOR ADDITIONAL REQUIREMENTS.
- B. COORDINATE AND PROVIDE SLEEVE LAYOUTS FOR ALL PIPES, CONDUITS, OR ANY OTHER ITEMS PENETRATING THROUGH STRUCTURAL MEMBERS. LAYOUTS ARE TO BE SUBMITTED TO AND APPROVED BY THE ENGINEER OF RECORD PRIOR TO CONSTRUCTION.



**III. GEOTECHNICAL NOTES**

- A. THE FOUNDATIONS FOR THIS STRUCTURE WE REDESIGNED BASED UPON THE PRESUMPTIVE ALLOWABLE VALUES AS DESCRIBED IN THE 2009 INTERNATIONAL BUILDING CODE, TABLE 1806.2 "PRESUMPTIVE LOAD-BEARING VALUES" FOR CLAY, SANDY CLAY, SILTY CLAY, CLAYEY SILT, SILT, AND SANDY SILT. SHOULD ACTUAL SITE CONDITIONS VARY FROM THIS, THE FOUNDATION SHALL BE REDESIGNED.

**IV. REINFORCED CONCRETE NOTES**

- A. ALL REINFORCED CONCRETE SHALL CONFORM TO ALL REQUIREMENTS OF ACI 301 "SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS", LATEST EDITION INCLUDING AMENDMENTS, AND ACI 318 "BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE", EDITION REFERENCED IN THE 2009 INTERNATIONAL BUILDING CODE.
- B. TOLERANCES FOR CONCRETE MEMBERS AND COMPONENTS SHALL CONFORM TO ACI 117 "SPECIFICATION FOR TOLERANCES FOR CONCRETE CONSTRUCTION AND MATERIALS."
- C. DETAILING OF CONCRETE REINFORCEMENT AND ACCESSORIES SHALL CONFORM TO ACI 315 "DETAILS AND DETAILING OF CONCRETE REINFORCEMENT."
- D. U.N.O., CONCRETE SHALL HAVE SAND AND CRUSHED STONE OR GRAVEL AGGREGATE AND TYPE I, II, OR III PORTLAND CEMENT. THE CONCRETE SHALL HAVE A MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 3,500 PSI AND A MAXIMUM WATER/CEMENTITIOUS MATERIALS RATIO OF 0.50, AND SHALL BE AIR ENTRAINED WITH AIR CONTENT OF 6% ±1.5%.
- E. NORMAL WEIGHT AGGREGATE SHALL CONFORM TO ASTM C33.
- F. SLUMP OF CONCRETE SHALL NOT EXCEED 3" AT THE END OF THE TRUCK OR PUMP HOSE (PER ACI 211.1 TABLE 6.3.1). SLUMP LOSS DUE TO PUMPING SHALL BE ACCOMMODATED. IF A SUPERPLASTICIZER OR MID-RANGE WATER REDUCING ADMIXTURE IS USED IN THE MIX DESIGN, THE SLUMP SHALL NOT EXCEED 8" AFTER ADDITION OF THE ADMIXTURE. DO NOT ADD WATER TO CONCRETE AFTER ADDING WATER-REDUCING ADMIXTURES TO THE MIX.
- G. U.N.O., ALL CONCRETE REINFORCING BARS SHALL CONFORM TO ASTM A615, GRADE 60 AND BE OF DOMESTIC MANUFACTURE. REINFORCING BARS TO BE WELDED SHALL CONFORM TO THE REQUIREMENTS OF ASTM A706, GRADE 60. WELDING TO REINFORCING BARS NOT SHOWN ON THE DRAWINGS, SHALL NOT BE PERMITTED. ELECTRICAL GROUNDING AND OTHER REQUIRED CONNECTIONS TO REINFORCING BARS SHALL BE ATTAINED VIA CLAMPS OR OTHER MANUFACTURED CONNECTIONS.
- H. REINFORCING SHALL BE SUPPORTED AND SECURED IN ITS PROPER LOCATION TO PREVENT DISPLACEMENT DURING PLACEMENT OF CONCRETE.
- I. THE CONTRACTOR SHALL VERIFY WITH ALL DISCIPLINES THE LOCATIONS OF ALL REQUIRED OPENINGS, SLEEVES, CAST-IN-PLACE ANCHORS OR HANGERS, SLAB DEPRESSIONS, INSERTS AND ANY OTHER ITEM TO BE CAST INTO THE CONCRETE.
- J. ALL HIGH-STRENGTH GROUT SHALL BE PREPACKAGED, NON-METALLIC, AND NON-GASEOUS. IT SHALL BE NON-SHRINK ACCORDING TO ASTM C-1107 OR CRD-C-821. GROUT SHALL OBTAIN A MINIMUM COMPRESSIVE STRENGTH OF 7,000 PSI IN 28 DAYS AND SHALL NOT BLEED. GROUT SHALL BE MOIST CURED FOR A MINIMUM OF 24 HOURS AFTER PLACEMENT. SUBMIT CERTIFIED, INDEPENDENT TEST DATA FOR APPROVAL.

**PARKING LOT LIGHT POLE FOUNDATION  
(WITH INTEGRATED BASE)**




**LIGHT POLE REACTIONS AT T.O. FOUNDATION**

POLE SIZE	BENDING MOMENT (FT/LBS)	TORSION (FT/LBS)	SHEAR FORCE (LBS)	AXIAL FORCE (LBS)
REFER LIGHT POLE DESCRIPTIONS	17,596	1149	1089	1055

**NOTES:**  
REACTIONS TO FOUNDATIONS SHOWN ARE A PROVIDED BY LIGHT MANUFACTURER. THE WORSE CASE LOADING IS NOTED. SHOULD THIS REACTION FROM ANY FIXTURE EXCEED THE VALUES NOTED, THE FOUNDATIONS SHALL BE RE-EVALUATED.

**LIGHT POLE DESCRIPTIONS**  
POLE BASE: STANDARD BASE (NO CLAMHELL)  
POLE: NY S 23 FTB 17 P10 ABG BZ  
POLE ARMS: ATC51/1CADBH-QSM OR ATC102/2CADBH-QSM  
BANNERS ARMS: (2) OR (4) BA30BH4BZ  
FIXTURES: (1) OR (2) ESL P30S 40K AS BZ TG 3 S BHDF13 200 BZ



CEC CORPORATION  
1655 W. MEMORIAL ROAD  
OKLAHOMA CITY, OKLAHOMA 73142  
P. 405.533.8200  
WWW.CONNECTCEC.COM  
STATE OF OK CERTIFICATE OF AUTHORIZATION  
COUNCIL NO. 22 EXPIRES 2018  
THIS DRAWING IS THE PROPERTY OF CEC. ANY  
REPRODUCTION OR USE OF THIS DRAWING  
WITHOUT THE PERMISSION OF  
CEC IS PROHIBITED.



REVISION HISTORY	DATE	DESCRIPTION
100% CONSTRUCTION DOCUMENTS	03/11/2016	FDN. SIZE & COL. BASE REV.
	14/25-16	C.L.S.
	04/04/2018	J.D.H.
		C.L.S.
		AS NOTED

**OSU ROADWAY/PARKING LIGHT POLE FOUNDATIONS**  
STILLWATER, OKLAHOMA

FOUNDATION DETAILS

SHEET  
**S2**



**GENERAL NOTES**

**PEDESTRIAN WALKWAY LIGHT POLE FOUNDATIONS**

**I. OVERALL NOTES**

- A. PRIOR TO BEGINNING ANY WORK OR ORDERING ANY MATERIALS, THE CONTRACTOR SHALL COORDINATE THE STRUCTURAL DRAWINGS WITH ALL OTHER TRADES, NOTIFY THE OWNER AND THE ENGINEER OF RECORD OF ANY DISCREPANCIES OR POSSIBLE DEFICIENCIES.
- B. PRIOR TO STARTING WORK, THE CONTRACTOR SHALL VERIFY THE EXISTING SITE CONDITIONS AND CONSTRAINTS AS WELL AS EXISTING BUILDING LOCATION, DIMENSIONS, AND ELEVATIONS, IF ANY.
- C. NO FIELD REVISIONS OR MODIFICATIONS TO ANY STRUCTURAL COMPONENT SHALL BE PERFORMED WITHOUT PRIOR APPROVAL BY THE ENGINEER OF RECORD.
- D. PLANS AND DETAILS SHALL NOT BE SCALED FOR DETERMINATION OF LENGTHS, QUANTITIES, OR CONFIGURATION OF MATERIALS.

**II. COORDINATION WITH OTHER TRADES**


- A. THE CONTRACTOR SHALL SUPPLY ALL ITEMS FOR ATTACHING MECHANICAL AND ELECTRICAL EQUIPMENT TO THE STRUCTURE TO RESIST ALL LOADS, INCLUDING SEISMIC FORCES. COORDINATE THE LOCATION(S) AND REQUIRED ATTACHMENT(S) WITH THE STRUCTURE. REFER TO THE ELECTRICAL AND MECHANICAL DOCUMENTS FOR ADDITIONAL REQUIREMENTS.
- B. COORDINATE AND PROVIDE SLEEVE LAYOUTS FOR ALL PIPES, CONDUITS, OR ANY OTHER ITEMS PENETRATING THROUGH STRUCTURAL MEMBERS. LAYOUTS ARE TO BE SUBMITTED TO AND APPROVED BY THE ENGINEER OF RECORD PRIOR TO CONSTRUCTION.

**III. GEOTECHNICAL NOTES**


- A. THE FOUNDATIONS FOR THIS STRUCTURE WE REDESIGNED BASED UPON THE PRESUMPTIVE ALLOWABLE VALUES AS DESCRIBED IN THE 2009 INTERNATIONAL BUILDING CODE, TABLE 1806.2 "PRESUMPTIVE LOAD-BEARING VALUES" FOR CLAY, SANDY CLAY, SILTY CLAY, CLAYEY SILT, SILT, AND SANDY SILT. SHOULD ACTUAL SITE CONDITIONS VARY FROM THIS, THE FOUNDATION SHALL BE REDESIGNED.

**IV. REINFORCED CONCRETE NOTES**

- A. ALL REINFORCED CONCRETE SHALL CONFORM TO ALL REQUIREMENTS OF ACI 301 "SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS", LATEST EDITION INCLUDING AMENDMENTS, AND ACI 318 "BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE", EDITION REFERENCED IN THE 2009 INTERNATIONAL BUILDING CODE.
- B. TOLERANCES FOR CONCRETE MEMBERS AND COMPONENTS SHALL CONFORM TO ACI 117 "SPECIFICATION FOR TOLERANCES FOR CONCRETE CONSTRUCTION AND MATERIALS."
- C. DETAILING OF CONCRETE REINFORCEMENT AND ACCESSORIES SHALL CONFORM TO ACI 315 "DETAILS AND DETAILING OF CONCRETE REINFORCEMENT."
- D. U.N.O., CONCRETE SHALL HAVE SAND AND CRUSHED STONE OR GRAVEL AGGREGATE AND TYPE I, II, OR III PORTLAND CEMENT. THE CONCRETE SHALL HAVE A MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 3,500 PSI AND A MAXIMUM WATER/CEMENTITIOUS MATERIALS RATIO OF 0.50, AND SHALL BE AIR ENTRAINED WITH AIR CONTENT OF 6% ±1.5%.
- E. NORMAL WEIGHT AGGREGATE SHALL CONFORM TO ASTM C33.
- F. SLUMP OF CONCRETE SHALL NOT EXCEED 3" AT THE END OF THE TRUCK OR PUMP HOSE (PER ACI 211.1 TABLE 6.3.1). SLUMP LOSS DUE TO PUMPING SHALL BE ACCOMMODATED. IF A SUPERPLASTICIZER OR MID-RANGE WATER REDUCING ADMIXTURE IS USED IN THE MIX DESIGN, THE SLUMP SHALL NOT EXCEED 8" AFTER ADDITION OF THE ADMIXTURE. DO NOT ADD WATER TO CONCRETE AFTER ADDING WATER-REDUCING ADMIXTURES TO THE MIX.
- G. U.N.O., ALL CONCRETE REINFORCING BARS SHALL CONFORM TO ASTM A615, GRADE 60 AND BE OF DOMESTIC MANUFACTURE. REINFORCING BARS TO BE WELDED SHALL CONFORM TO THE REQUIREMENTS OF ASTM A706, GRADE 60. WELDING TO REINFORCING BARS NOT SHOWN ON THE DRAWINGS, SHALL NOT BE PERMITTED. ELECTRICAL GROUNDING AND OTHER REQUIRED CONNECTIONS TO REINFORCING BARS SHALL BE ATTAINED VIA CLAMPS OR OTHER MANUFACTURED CONNECTIONS.
- H. REINFORCING SHALL BE SUPPORTED AND SECURED IN ITS PROPER LOCATION TO PREVENT DISPLACEMENT DURING PLACEMENT OF CONCRETE.
- I. THE CONTRACTOR SHALL VERIFY WITH ALL DISCIPLINES THE LOCATIONS OF ALL REQUIRED OPENINGS, SLEEVES, CAST-IN-PLACE ANCHORS OR HANGERS, SLAB DEPRESSIONS, INSERTS AND ANY OTHER ITEM TO BE CAST INTO THE CONCRETE.
- J. ALL HIGH-STRENGTH GROUT SHALL BE PREPACKAGED, NON-METALLIC, AND NON-GASEOUS. IT SHALL BE NON-SHRINK ACCORDING TO ASTM C-1107 OR CRD-C-821. GROUT SHALL OBTAIN A MINIMUM COMPRESSIVE STRENGTH OF 7,000 PSI IN 28 DAYS AND SHALL NOT BLEED. GROUT SHALL BE MOIST CURED FOR A MINIMUM OF 24 HOURS AFTER PLACEMENT. SUBMIT CERTIFIED, INDEPENDENT TEST DATA FOR APPROVAL.



**(WITH BOLLARD)**



**(WITHOUT BOLLARD)**


**USE THIS DESGIN UNLESS OTHERWISE INSTRUCTED BY ESUE**

LIGHT POLE REACTIONS AT T.O. FOUNDATION				
POLE SIZE	BENDING MOMENT (FT/LBS)	TORSION (FT/LBS)	SHEAR FORCE (LBS)	AXIAL FORCE (LBS)
REFER LIGHT POLE DESCRIPTIONS	1666.43	---	220.20	212.32

NOTES:  
REACTIONS TO FOUNDATIONS SHOWN ARE A PROVIDED BY LIGHT MANUFACTURER. THE WORSE CASE LOADING IS NOTED. SHOULD THIS REACTION FROM ANY FIXTURE EXCEED THE VALUES NOTED, THE FOUNDATIONS SHALL BE RE-EVALUATED.

**LIGHT POLE DESCRIPTIONS**

- POLE BASE: 17" ROUND (SITELINK BASE) - CLAMSHHELL BASE
- POLE: NYA 14 L5J 17 (SITELINK BASE) P07 ABG BZ
- FIXTURES: PTUE 100 4K AS G3 Z S



CEC CORPORATION  
1655 W. MEMORIAL ROAD  
OKLAHOMA CITY, OKLAHOMA 73142  
P. 405.523.8200  
WWW.CONNECTCEC.COM

STATE OF OK CERTIFICATE OF AUTHORIZATION  
CHRISTOPHER SWIDER  
3-9-2018  
23089

OKLAHOMA PROFESSIONAL ENGINEER



REVISION HISTORY	
DATE	DESCRIPTION

100% CONSTRUCTION DOCUMENTS	
DATE	DESCRIPTION
03/11/2016	
14/27/16	

SUBMITTAL:	
DATE	DESCRIPTION

**OSU PEDESTRIAN WALKWAY LIGHT POLE FOUNDATIONS**

STILLWATER, OKLAHOMA

FOUNDATION DETAILS

SHEET  
**S3**

# GENERAL NOTES

## I. OVERALL NOTES

- A. PRIOR TO BEGINNING ANY WORK OR ORDERING ANY MATERIALS, THE CONTRACTOR SHALL COORDINATE THE STRUCTURAL DRAWINGS WITH ALL OTHER TRADES. NOTIFY THE OWNER AND THE ENGINEER OF RECORD OF ANY DISCREPANCIES OR POSSIBLE DEFICIENCIES.
- B. PRIOR TO STARTING WORK, THE CONTRACTOR SHALL VERIFY THE EXISTING SITE CONDITIONS AND CONSTRAINTS AS WELL AS EXISTING BUILDING LOCATION, DIMENSIONS, AND ELEVATIONS, IF ANY.
- C. NO FIELD REVISIONS OR MODIFICATIONS TO ANY STRUCTURAL COMPONENT SHALL BE PERFORMED WITHOUT PRIOR APPROVAL BY THE ENGINEER OF RECORD.
- D. PLANS AND DETAILS SHALL NOT BE SCALED FOR DETERMINATION OF LENGTHS, QUANTITIES, OR CONFIGURATION OF MATERIALS.

## II. COORDINATION WITH OTHER TRADES

- A. THE CONTRACTOR SHALL SUPPLY ALL ITEMS FOR ATTACHING MECHANICAL AND ELECTRICAL EQUIPMENT TO THE STRUCTURE TO RESIST ALL LOADS, INCLUDING SEISMIC FORCES. COORDINATE THE LOCATION(S) AND REQUIRED ATTACHMENT(S) WITH THE STRUCTURE. REFER TO THE ELECTRICAL AND MECHANICAL DOCUMENTS FOR ADDITIONAL REQUIREMENTS.
- B. COORDINATE AND PROVIDE SLEEVE LAYOUTS FOR ALL PIPES, CONDUITS, OR ANY OTHER ITEMS PENETRATING THROUGH STRUCTURAL MEMBERS. LAYOUTS ARE TO BE SUBMITTED TO AND APPROVED BY THE ENGINEER OF RECORD PRIOR TO CONSTRUCTION.

## III. GEOTECHNICAL NOTES

- A. THE FOUNDATIONS FOR THIS STRUCTURE WE REDESIGNED BASED UPON THE PRESUMPTIVE ALLOWABLE VALUES AS DESCRIBED IN THE 2009 INTERNATIONAL BUILDING CODE, TABLE 1806.2 "PRESUMPTIVE LOAD-BEARING VALUES" FOR CLAY, SANDY CLAY, SILTY CLAY, CLAYEY SILT, SILT, AND SANDY SILT. SHOULD ACTUAL SITE CONDITIONS VARY FROM THIS, THE FOUNDATION SHALL BE REDESIGNED.


## IV. REINFORCED CONCRETE NOTES

- A. ALL REINFORCED CONCRETE SHALL CONFORM TO ALL REQUIREMENTS OF ACI 301 "SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS", LATEST EDITION INCLUDING AMENDMENTS, AND ACI 318 "BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE", EDITION REFERENCED IN THE 2009 INTERNATIONAL BUILDING CODE.
- B. TOLERANCES FOR CONCRETE MEMBERS AND COMPONENTS SHALL CONFORM TO ACI 117 "SPECIFICATION FOR TOLERANCES FOR CONCRETE CONSTRUCTION AND MATERIALS."
- C. DETAILING OF CONCRETE REINFORCEMENT AND ACCESSORIES SHALL CONFORM TO ACI 315 "DETAILS AND DETAILING OF CONCRETE REINFORCEMENT."
- D. U.N.O., CONCRETE SHALL HAVE SAND AND CRUSHED STONE OR GRAVEL AGGREGATE AND TYPE I, II, OR III PORTLAND CEMENT. THE CONCRETE SHALL HAVE A MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 3,500 PSI AND A MAXIMUM WATER/CEMENTITIOUS MATERIALS RATIO OF 0.50, AND SHALL BE AIR ENTRAINED WITH AIR CONTENT OF 6% ±1.5%.
- E. NORMAL WEIGHT AGGREGATE SHALL CONFORM TO ASTM C33.
- F. SLUMP OF CONCRETE SHALL NOT EXCEED 3" AT THE END OF THE TRUCK OR PUMP HOSE (PER ACI 211.1 TABLE 6.3.1). SLUMP LOSS DUE TO PUMPING SHALL BE ACCOMMODATED. IF A SUPERPLASTICIZER OR MID-RANGE WATER REDUCING ADMIXTURE IS USED IN THE MIX DESIGN, THE SLUMP SHALL NOT EXCEED 8" AFTER ADDITION OF THE ADMIXTURE. DO NOT ADD WATER TO CONCRETE AFTER ADDING WATER-REDUCING ADMIXTURES TO THE MIX.
- G. U.N.O., ALL CONCRETE REINFORCING BARS SHALL CONFORM TO ASTM A615, GRADE 60 AND BE OF DOMESTIC MANUFACTURE. REINFORCING BARS TO BE WELDED SHALL CONFORM TO THE REQUIREMENTS OF ASTM A706, GRADE 60. WELDING TO REINFORCING BARS NOT SHOWN ON THE DRAWINGS, SHALL NOT BE PERMITTED. ELECTRICAL GROUNDING AND OTHER REQUIRED CONNECTIONS TO REINFORCING BARS SHALL BE ATTAINED VIA CLAMPS OR OTHER MANUFACTURED CONNECTIONS.
- H. REINFORCING SHALL BE SUPPORTED AND SECURED IN ITS PROPER LOCATION TO PREVENT DISPLACEMENT DURING PLACEMENT OF CONCRETE.
- I. THE CONTRACTOR SHALL VERIFY WITH ALL DISCIPLINES THE LOCATIONS OF ALL REQUIRED OPENINGS, SLEEVES, CAST-IN-PLACE ANCHORS OR HANGERS, SLAB DEPRESSIONS, INSERTS AND ANY OTHER ITEM TO BE CAST INTO THE CONCRETE.
- J. ALL HIGH-STRENGTH GROUT SHALL BE PREPACKAGED, NON-METALLIC, AND NON-GASEOUS. IT SHALL BE NON-SHRINK ACCORDING TO ASTM C-1107 OR CRD-C-821. GROUT SHALL OBTAIN A MINIMUM COMPRESSIVE STRENGTH OF 7,000 PSI IN 28 DAYS AND SHALL NOT BLEED. GROUT SHALL BE MOIST CURED FOR A MINIMUM OF 24 HOURS AFTER PLACEMENT. SUBMIT CERTIFIED, INDEPENDENT TEST DATA FOR APPROVAL.

## BOLLARD DESCRIPTIONS

- BOLLARD: BOL/NY44/20/L/CI/DB/L100  
NORTH YORKSHIRE CAST IRON BOLLARD WITH DARK BRONZE FINISH AND 100W/208V LED LAMP, CLEAR LENS WITH DOWNWARD LOUVERED REFLECTORS.

# BOLLARD LIGHT FOUNDATIONS



**CEC**  
Infrastructure Solutions

CEC CORPORATION  
1655 W. MEMORIAL ROAD  
OKLAHOMA CITY, OKLAHOMA 73142  
P. 405.523.8200  
WWW.CONNECTCEC.COM

STATE OF OK CERTIFICATE OF AUTHORIZATION  
CHRISTOPHER SNIDER  
C.P.E. - 36187  
C.E.P. - 2018  
THIS DRAWING IS THE PROPERTY OF CEC. ANY  
REPRODUCTION OR USE OF THIS DRAWING  
WITHOUT THE PERMISSION OF  
CEC IS PROHIBITED.

CHRISTOPHER SNIDER  
3-9-2018  
23089  
OKLAHOMA

SUBMITTAL:	100% CONSTRUCTION DOCUMENTS		REVISION HISTORY	
	DATE:	PROJECT NO:	DATE	DESCRIPTION
DATE:	03/11/2016	14275-16		
DESIGNED BY:	C.L.S.	J.D.H.		
DRAWN BY:	C.L.S.	C.L.S.		
APPROVED BY:	AS NOTED			
SCALE:				

OSU BOLLARD LIGHT FOUNDATIONS

STILLWATER, OKLAHOMA

FOUNDATION DETAILS

SHEET

S4



**GENERAL NOTES**

**I. OVERALL NOTES**

- A. PRIOR TO BEGINNING ANY WORK OR ORDERING ANY MATERIALS, THE CONTRACTOR SHALL COORDINATE THE STRUCTURAL DRAWINGS WITH ALL OTHER TRADES. NOTIFY THE OWNER AND THE ENGINEER OF RECORD OF ANY DISCREPANCIES OR POSSIBLE DEFICIENCIES.
- B. PRIOR TO STARTING WORK, THE CONTRACTOR SHALL VERIFY THE EXISTING SITE CONDITIONS AND CONSTRAINTS AS WELL AS EXISTING BUILDING LOCATION, DIMENSIONS, AND ELEVATIONS, IF ANY.
- C. NO FIELD REVISIONS OR MODIFICATIONS TO ANY STRUCTURAL COMPONENT SHALL BE PERFORMED WITHOUT PRIOR APPROVAL BY THE ENGINEER OF RECORD.
- D. PLANS AND DETAILS SHALL NOT BE SCALED FOR DETERMINATION OF LENGTHS, QUANTITIES, OR CONFIGURATION OF MATERIALS.

**II. COORDINATION WITH OTHER TRADES**

- A. THE CONTRACTOR SHALL SUPPLY ALL ITEMS FOR ATTACHING MECHANICAL AND ELECTRICAL EQUIPMENT TO THE STRUCTURE TO RESIST ALL LOADS, INCLUDING SEISMIC FORCES. COORDINATE THE LOCATION(S) AND REQUIRED ATTACHMENT(S) WITH THE STRUCTURE. REFER TO THE ELECTRICAL AND MECHANICAL DOCUMENTS FOR ADDITIONAL REQUIREMENTS.
- B. COORDINATE AND PROVIDE SLEEVE LAYOUTS FOR ALL PIPES, CONDUITS, OR ANY OTHER ITEMS PENETRATING THROUGH STRUCTURAL MEMBERS. LAYOUTS ARE TO BE SUBMITTED TO AND APPROVED BY THE ENGINEER OF RECORD PRIOR TO CONSTRUCTION.


**III. GEOTECHNICAL NOTES**

- A. THE FOUNDATIONS FOR THIS STRUCTURE WE REDESIGNED BASED UPON THE PRESUMPTIVE ALLOWABLE VALUES AS DESCRIBED IN THE 2009 INTERNATIONAL BUILDING CODE, TABLE 1806.2 "PRESUMPTIVE LOAD-BEARING VALUES" FOR CLAY, SANDY CLAY, SILTY CLAY, CLAYEY SILT, SILT, AND SANDY SILT. SHOULD ACTUAL SITE CONDITIONS VARY FROM THIS, THE FOUNDATION SHALL BE REDESIGNED.

**IV. REINFORCED CONCRETE NOTES**

- A. ALL REINFORCED CONCRETE SHALL CONFORM TO ALL REQUIREMENTS OF ACI 301 "SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS", LATEST EDITION INCLUDING AMENDMENTS, AND ACI 318 "BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE", EDITION REFERENCED IN THE 2009 INTERNATIONAL BUILDING CODE.
- B. TOLERANCES FOR CONCRETE MEMBERS AND COMPONENTS SHALL CONFORM TO ACI 117 "SPECIFICATION FOR TOLERANCES FOR CONCRETE CONSTRUCTION AND MATERIALS."
- C. DETAILING OF CONCRETE REINFORCEMENT AND ACCESSORIES SHALL CONFORM TO ACI 315 "DETAILS AND DETAILING OF CONCRETE REINFORCEMENT."
- D. U.N.O., CONCRETE SHALL HAVE SAND AND CRUSHED STONE OR GRAVEL AGGREGATE AND TYPE I, II, OR III PORTLAND CEMENT. THE CONCRETE SHALL HAVE A MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 3,500 PSI AND A MAXIMUM WATER/CEMENTITIOUS MATERIALS RATIO OF 0.50, AND SHALL BE AIR ENTRAINED WITH AIR CONTENT OF 6% ±1.5%.
- E. NORMAL WEIGHT AGGREGATE SHALL CONFORM TO ASTM C33.
- F. SLUMP OF CONCRETE SHALL NOT EXCEED 3" AT THE END OF THE TRUCK OR PUMP HOSE (PER ACI 211.1 TABLE 6.3.1). SLUMP LOSS DUE TO PUMPING SHALL BE ACCOMMODATED. IF A SUPERPLASTICIZER OR MID-RANGE WATER REDUCING ADMIXTURE IS USED IN THE MIX DESIGN, THE SLUMP SHALL NOT EXCEED 8" AFTER ADDITION OF THE ADMIXTURE. DO NOT ADD WATER TO CONCRETE AFTER ADDING WATER-REDUCING ADMIXTURES TO THE MIX.
- G. U.N.O., ALL CONCRETE REINFORCING BARS SHALL CONFORM TO ASTM A615, GRADE 60 AND BE OF DOMESTIC MANUFACTURE. REINFORCING BARS TO BE WELDED SHALL CONFORM TO THE REQUIREMENTS OF ASTM A706, GRADE 60. WELDING TO REINFORCING BARS NOT SHOWN ON THE DRAWINGS, SHALL NOT BE PERMITTED. ELECTRICAL GROUNDING AND OTHER REQUIRED CONNECTIONS TO REINFORCING BARS SHALL BE ATTAINED VIA CLAMPS OR OTHER MANUFACTURED CONNECTIONS.
- H. REINFORCING SHALL BE SUPPORTED AND SECURED IN ITS PROPER LOCATION TO PREVENT DISPLACEMENT DURING PLACEMENT OF CONCRETE.
- I. THE CONTRACTOR SHALL VERIFY WITH ALL DISCIPLINES THE LOCATIONS OF ALL REQUIRED OPENINGS, SLEEVES, CAST-IN-PLACE ANCHORS OR HANGERS, SLAB DEPRESSIONS, INSERTS AND ANY OTHER ITEM TO BE CAST INTO THE CONCRETE.
- J. ALL HIGH-STRENGTH GROUT SHALL BE PREPACKAGED, NON-METALLIC, AND NON-GASEOUS. IT SHALL BE NON-SHRINK ACCORDING TO ASTM C-1107 OR CRD-C-821. GROUT SHALL OBTAIN A MINIMUM COMPRESSIVE STRENGTH OF 7,000 PSI IN 28 DAYS AND SHALL NOT BLEED. GROUT SHALL BE MOIST CURED FOR A MINIMUM OF 24 HOURS AFTER PLACEMENT. SUBMIT CERTIFIED, INDEPENDENT TEST DATA FOR APPROVAL.

**ROADWAY LIGHT POLE FOUNDATION WITH OBSTRUCTION AT DRILLED PIER (WITH CLAMSHELL BASE)**




**LIGHT POLE REACTIONS AT T.O. FOUNDATION**

POLE SIZE	BENDING MOMENT (FT/LBS)	TORSION (FT/LBS)	SHEAR FORCE (LBS)	AXIAL FORCE (LBS)
REFER LIGHT POLE DESCRIPTIONS	17,596	1149	1089	1055

NOTES:  
REACTIONS TO FOUNDATIONS SHOWN ARE A PROVIDED BY LIGHT MANUFACTURER. THE WORSE CASE LOADING IS NOTED. SHOULD THIS REACTION FROM ANY FIXTURE EXCEED THE VALUES NOTED, THE FOUNDATIONS SHALL BE RE-EVALUATED.

**LIGHT POLE DESCRIPTIONS**

POLE BASE: NY24CSBCADBH - (CLAMSHELL BASE)  
 POLE: FL210-700E210-P16-BZ, FL210-700E210-P16-(2)BAP-BZ, FL210-700E210-P16-(4)BAP-BZ  
 POLE ARMS: ATC51/1CADBH-QSM OR ATC102/2CADBH-QSM  
 BANNERS ARMS: (2) OR (4) BA30BOH4BZ  
 FIXTURES: (1) OR (2) ESL P30S 40K AS BZ TG 3 S BHDF13 200 BZ



CEC CORPORATION  
 1655 W. MEMORIAL ROAD  
 OKLAHOMA CITY, OKLAHOMA 73142  
 P. 405.933.8200  
 WWW.CONNECTCEC.COM

STATE OF OK CERTIFICATE OF AUTHORIZATION  
 CHRISTOPHER SNIDER  
 06-26-2018  
 23089

OKLAHOMA PROFESSIONAL ENGINEER



REVISION HISTORY	DATE	DESCRIPTION
100% CONSTRUCTION DOCUMENTS	08/25/2018	
	14/27/16	
		C.L.S.
		C.L.S.
		C.L.S.
		AS NOTED

**OSU BOLLARD LIGHT FOUNDATIONS**

STILLWATER, OKLAHOMA

FOUNDATION DETAILS

SHEET  
**S5**

## OSU STANDARD HOLOPHANE LIGHTING FIXTURES

### Poles:

Post Top Sitelink Pedestrian – North Yorkshire (NY), Aluminum (A), Height (14’), Shaft Size (L5J), Base Diameter – 17”, Tenon Size (3”x3”-PO7), Pole Mounting Options (ABG), Color (Bronze)

**#: NY A 14 L5J 17 PO7 ABG BZ**

Parking Lot Fluted – North Yorkshire (NY), Material- Steel (S), Height (21’), Shaft Style (FTB), Base-17”, Tenon P10 (3”x9”), Mounting-ABG, Finish-Bronze (BZ); Poles may also be Aluminum – No clamshell base (Parking Lots)

**#: NYS 21 FTB 17 P10 ABG BZ**

Roadway Fluted – North Yorkshire (NY), Material-Steel (S), Height (21’-4”), Shaft Style Round Tapered Fluted (12 Flat), Tenon (4.5” x 10”), (4) Banner Arm Provisions, Mounting 10.4” Butt Diameter Baseplate – 15” bolt circle, Color Dark Bronze (DB); Clamshell Base (CSB-24” Diameter, 42” Tall); CIS- Cast Iron Steel

**#: FL210-T40B210-4.5T10-BZ-(4)BAPADS - NY24CSBCIDBH** (Modified 3/2/2017)

### Mounting Arms:

Parking Lot Single Arm – West Liberty (WLC), 72”, Cast Aluminum (CA), Color Dark Bronze (DBH), Swivel-Dark Bronze (DBZ)

**#: WLC72/1 CA DBH \*WEST LIBERTY FITTER TO BE ORDERED WITH LUMINAIRE**

Parking Lot Double Arm – West Liberty (WLC), 144”, Cast Aluminum (CA), Color Dark Bronze (DBH), Swivel-Dark Bronze (DBZ)

**#: WLC144/2 CA DBH \*WEST LIBERTY FITTER TO BE ORDERED WITH LUMINAIRE**

Roadway Arms Single – **#:ATC51/1 CA DBH**

Roadway Arms Double – **#:ATC102/2 CA DBH**

### Luminaires:

#### Post Top LED – Utility Post top LED (PTUE), Wattage 100W, Color Temp 4K,

Voltage 120/277 (AS), Optics- Asymmetric glass refractor (GY3), Color-Bronze (BZ), Finial-Spike (S), Option-ADJUSTABLE OUTPUT (AO)

**#: PTUE2 P30 40K AS GL3 BZ S AO**

**Roadway** – Esplanade LED (ESL), Wattage 118W, Color Temp 4K, Voltage 120-277-AS or 347-480-AH, Top Entry- Stem Mount (S), Housing Color – Bronze (BZ), Optics-Teardrop Asymmetric (3), Adjustable Output (AO), Short Skirt (SS); with bronze Boston Harbor Fitter (BLDF13200 BZ) (? = Voltage Either AS or AH)

**Roadway #: ESL2 P30S 40K ? BZ TG 3 S AO SS BHDF13 200 BZ**

**Parking Lot** - Esplanade LED (ESL), Wattage 118W, Color Temp 4K, Voltage 120-277-AS or 347-480-AH, Top Entry- Stem Mount (S), Housing Color – Bronze (BZ), Optics-Teardrop Asymmetric (3), Adjustable Output (AO), Short Skirt (SS); with bronze West Liberty Fitter (WLD13 200 BZ) (? = Voltage Either AS or AH)

**Parking: # ESL2 P30S 40K ? BZ TG 3 S AO SS WLDF13 200 BZ**

**Bollard Lights:**

**Bollard with Convenience Outlet** - BOLLARD SHAFT Columbia Lighted Bollard (BOLC), 3'-8" Height, 13" Diameter Base, Internal Light And White Lens, Cast Aluminum, Dark Bronze, INCANDESCENT, MEDIUM BASE SOCKET, 120 Volt, RECEPTACLE PROVISION GFI RECEPTACLE WITH WEATHERPROOF WHILE CLOSED COVER. HOLOPHANE BRONZE 3/4"X18" ANCHOR BOLTS INCLUDED

**BOLC4413LWCADBHINC120-RXXXY FG-SDBH AB-31-4 RFD267273**

**Options:**

Banner Arms – *BA30 BO H 4 BZ* (Banner Arm 30", Bolt On, Finial-Half Sphere (H), 1" diameter (4), Bronze (BZ))

**Contractor Installed in Base:**

Slow-Blow In-line fuses

**All post top lights and bollard lights are typically 120V. All parking lot and roadway lights are typically 480V single phase.**





## Facilities Management

Energy Services  
220 Central Plant  
Stillwater, Oklahoma 74078-8026  
Office (405) 744-7131  
<http://utilities.okstate.edu>

### OSU EXTERIOR LIGHTING STANDARDS

September 12, 2018

OSU has adopted the following illumination standards for outdoor spaces from the IESNA Recommended Practices, Design Guides, Guidelines, the 10<sup>th</sup> Edition Lighting Handbook and the 2013 OSU Exterior Lighting Study. All parking lots and pedestrian pathways on the campus are considered to be "Secure", which requires maintaining a more even uniformity ratio for the areas.

#### **Parking Lots (All)**

- 3 foot candle minimum maintained horizontal and vertical average at 5'-0" above grade
- Minimum maintained foot candle reading of no less than .7
- Maximum maintained foot candle reading of 10.5
- Average to minimum ratio no greater than 4:1
- Maximum to minimum ratio no greater than 15:1

#### **Roadways/Street (All on/around Campus)**

- 1 foot candle minimum maintained horizontal average
- Minimum foot candle reading of no less than .25
- Average to minimum ratio no greater than 4:1

#### **Sidewalks and Pedestrian Pathways (All on/around Campus)**

- 1 foot candle horizontal average
- Minimum foot candle reading of no less than .25
- Average to minimum ratio no greater than 4:1

Illumination plots shall be calculated on a 5'x5' grid spacing. The illumination plot shall show fixture placement and statistics including average, minimum, maximum, average-to-minimum ratio and maximum-to-minimum ratio for each calculation zone.

Coordinate all intersection and crosswalk lighting designs with OSU Energy Services – Utilities Engineering.

#### References

- IESNA RP-20-14 Revised, Part II, Section 7
- IESNA RP-8-14
- IESNA G-1-16, Section 8.2.6; Section 8.2.16

The following suite of standardized light fixtures describes the aesthetic properties of the light assemblies only. Detailed specifications for lighting standards can be found in the Oklahoma State University Building Design Standards - Section 16530, Exterior Lighting Fixtures:

**Street Light Assembly - Single Fixture:**

- Manufacturer - Holophane®
- Pole - SiteLink® Pole, 5.75" Fluted Aluminum, 24" North Yorkshire Base, 21" Height, Black Color
- Fixture - Esplanade Tear Drop, Decorative Shallow Skirt, West Liberty Leveling Fitter, Black Color
- Cross Arm - ATC Single Arm
- Banner Arms - Two 30" Long Banner Arms, Black Color

**Street Light Assembly - Double Fixture:**

- Manufacturer - Holophane®
- Pole - SiteLink® Pole, 5.75" Fluted Aluminum, 24" North Yorkshire Base, 21" Height, Black Color
- Fixture - Esplanade Tear Drop, Decorative Shallow Skirt, West Liberty Leveling Fitter, Black Color
- Cross Arm - West Liberty Twin Crossarm
- Banner Arms - Four 30" Long Banner Arms, Black Color

**Parking Lot Light Assembly - Double Fixture:**

- Manufacturer - Holophane®
- Pole - SiteLink® Pole, 5.75" Fluted Aluminum, 24" North Yorkshire Base, 21" Height, Black Color
- Fixture - Esplanade Tear Drop, Decorative Shallow Skirt, West Liberty Leveling Fitter, Black Color
- Cross Arm - West Liberty Twin Crossarm
- Banner Arms - Four 30" Long Banner Arms, Black Color
- Notes - Same assembly as the Double Fixture Street Light

**Pedestrian Light Assembly:**

- Manufacturer - Holophane®
- Pole - SiteLink® Pole, 4.5" Fluted Aluminum, 17" North Yorkshire Base, 12" Height, Dark Bronze Color
- Fixture - Utility Postop, Full Cutoff, Spike Finial, Black Color
- Banner Arms - Four 18" Long Banner Arms, Black Color

**Lighted Bollard:**

- Manufacturer - Holophane®
- Model - Columbia™, 44" Height, 13" Diameter Base
- Material - Cast Aluminum or Cast Iron
- Color - Black Powder Coat
- Notes - Lighted bollards match non-lighted bollards (see Site Furnishings)

